



G100W G-Series Drainage Composite

G100W Drainage Composite is produced from a high compressive strength core with a Mirafi® monofilament FW402 filter geotextile bonded to one side.

TenCate Geosynthetics Americas Laboratories are accredited by Geosynthetic Accreditation Institute – Laboratory Accreditation Program (GAI-LAP).

Core Mechanical Properties	Test Method	Unit	Typical Roll Value	
Thickness	ASTM D1777	in (mm)	0.4 (10.2)	
Compressive Strength	ASTM D1621	psf (kPa)	18,000 (861)	
Maximum Flow Rate ¹	ASTM D4716	gal/min/ft (l/min/m)	21 (260)	
Installed Vertically Flow Rate ²	ASTM D4716	gal/min/ft (l/min/m)	18 (224)	
Installed Horizontally Flow Rate ³	ASTM D4716	gal/min/ft (l/min/m)	3.8 (47)	

¹ In plane flow rate at 173 kPa (3600 psf) with a gradient of 1.0

³ Installed flow rate with soil overburden at a horizontal gradient of 0.05

Geotextile Mechanical Properties Mirafi® FW402	Test Method	Unit	Minimum Average Roll Value	
			MD	CD
Grab Tensile Strength	ASTM D4632	lbs (N)	365 (1624)	200 (890)
CBR Puncture Strength	ASTM D6241	lbs (N)	675 (3004)	
Apparent Opening Size (AOS)	ASTM D4751	U.S. Sieve (mm)	40 (0.425)	
Percent Open Area	COE-02215	%	10	
Permittivity	ASTM D4491	sec ⁻¹	2.1	
Flow Rate	ASTM D4491	gal/min/ft ² (l/min/m ²)	145 (5907)	

Physical Properties	Unit	Typical Value
Roll Dimensions (width x length)	ft (m)	4.0 x 50 (1.2 x 15.2)
Roll Area	ft ² (m ²)	200 (18.6)
Estimated Roll Weight	lb (kg)	50 (23)

Disclaimer: TenCate assumes no liability for the accuracy or completeness of this information or for the ultimate use by the purchaser. TenCate disclaims any and all express, implied, or statutory standards, warranties or guarantees, including without limitation any implied warranty as to merchantability or fitness for a particular purpose or arising from a course of dealing or usage of trade as to any equipment, materials, or information furnished herewith. This document should not be construed as engineering advice.

Mirafi® is a registered trademark of Nicolon Corporation.

Copyright © 2015 Nicolon Corporation. All Rights Reserved.





² Installed flow rate with soil overburden at a vertical gradient of 1.0